BRUHATH BANGALORE MAHANAGARA PALIKE
DTS

Issued to Sri

TEND NO:
ITEM NO:
Orginal/Duplicate

NAME OF WORK: Construction of RCC Drain at 11th Cross of Muthyala Nagara in Ward No.17

Sl. No	Qty	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	297.00	Earthwork excavation for foundtion of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	cum		
2	297.00	Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	cum		
3	49.50	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregate @0.85 cum and fine aggregate @0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum		
4	94.50	Providing andlaying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates @ 0.459 cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed -2008, machine mixed, concrete laid in layres not exceeding 15 cms, thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase,lintles, retaining walls, return walls, walls (any thickness) includng attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills fillets etc, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum		

Nil & Corrections – Nil –

D.T.S. Approved

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ ವಿಭಾಗ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಬೆಂಗಳೂರು-560 077

	61.43	Providing T.M.T Steel reinforcement for RCC Work including straightening, cutting, bending hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wasstge shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	qtl		
6	720.00	Providing and removing centering, shuttering, strutting proppoing etc, and removal of formwork for Vertical surface such as walls at any thickness including attached pilasters butresses, plinth and string courses cost of all materials, labour complete as per specifications.	sqm		
7	270.00	Providing 10 cm thick granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.	sqm		
8	270.00	Providing one line dressing to granite stone slabs / granitestone masonary as per specifications	sqm		
9	1428.00	Providing chamfering edges to stone slabs 2.5 cms, wide as per specifications (only chamfered length shall be recorded)	rmt		
10	667.00	Providing and fixing Pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with toop and bottom wideth 114 and 165 mm respectively 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, includng form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unoading lead and lift transportatin etc, complete.	nos		
11	135.00	Providing and applying ready mix priming coat over concrete/ masonry/asbestos cement sheet/ plastered surfaces including preparing the surface after thoroughly cleaning of oil grease, dirt and other foreign matter, and sand preparing including cost of materials, labour complete as per specifications	sqm		
12	135.00	Providing and applying floor painting with ready mix paint in two coats (excluding primer coat) on new concrete/asbestos cement sheet/plastered surfaces brushing to give an even shade after preparing the surface after througly cleaning oil dirt, dust other foreign matter and sand papering including cost of all materials, labour complete as per specifications.	sqm		

N/R of Corrections – Nil –

D.T.S. Approved

Executive Engineer
Rajarajeshwarinagara Division
B.B.M.P